

Phase 2 Achievements

March 19 - July 17, 2018

Y. Ohnishi

Kaminari-mon Gate





Senso-ji (Buddist temple), Tokyo



Kaminari-mon Gate



Senso-ji (Buddhist temple), Tokyo



浅草寺観音籤

第十一大吉

有禄興家業 幸いや収入が身に備わり、家業もおいおい栄えるでしょう。	願事：十分に叶うでしょう。 病気：治るでしょう。
文華達帝都 才能が現われてきて、世間の評判となることでしょう。	失物：見つかるでしょう。 待ち人：現れるでしょう。
雲中乗好箭 空へ矢を放ったとしても良い獲物が得られるように、何事にも成功するでしょう。	新築・転居：良いでしょう。 旅行：問題ないでしょう。
兼得貴人扶 これ程の幸せに加えて、また目上の人や神仏の助けが得られるでしょう。	結婚・付き合い：全て良い結果が得られるでしょう。

No.11 BEST FORTUNE

You can get both treasure and dignity. Your family business will be really prosperous. Your skill will extremely develop and will be well-known to the people even in the capital.

Shooting arrows to the sky brings you big game. You are happy as mentioned above, you can also get help and assistance of gods.

*Your wishes will be realized. *A sick person will recover. *The lost article will be found. *The person you are waiting for will come. *Building and removal are good. *Making a trip is all right. *Marriage and employment are all good.

「浅草寺観音籤」の由来と心得

御籤の習俗はそのむかし中国より伝えられ、比叡山において、日本独特の吉凶を占う百番の御籤となりました。当初は関西方面で広まりましたが、江戸時代には関東にも広がり、庶民向けに改められて今日の「浅草寺観音籤」となりました。
観音籤には一番から百番まであり、その吉凶判断には凶・吉・末吉・半吉・小吉・末小吉・大吉の7種類があります。この中、大吉が出たからといって油断をしたり、また高慢な態度をとれば、凶に転じることもあります。謙虚で柔和な気持で人々に接するようにしましょう。また凶が出た人も畏（おそれ）ることなく、辛抱強さをもって誠実に過ごすことで、吉に転じます。凶の出た人は観音様のご加護を願い、境内の指定場所にこの観音籤を結んで、ご縁つなぎをしてください。

あさくさかんのん 浅草寺


1. Verification of nano-beam scheme


- Squeezing β_y^* down to a few mm $< \sigma_z$.
- Luminosity increases even though β_y^* is smaller than σ_z .
- Beam-Beam parameter, $\xi_y > 0.03$
- $L = 10^{34} \text{ cm}^{-2}\text{s}^{-1}$ at 1 [A] beam current in the LER


2. Understanding and reduction of Belle II backgrounds


3. Establishment of the injection system


Target	Achievements	Remark
Squeezing β_y^* down to 2 mm	$\beta_y^* = 3$ mm	$\beta_y^* = 2$ mm is tested for machine study
Luminosity increases even though $\beta_y^* < \sigma_z$.	confirmed	XY coupling at the IP is adjusted by QC1.
Beam-Beam Parameter, $\xi_y > 0.03$	$\xi_{y-} = 0.021$ at $I_{b+} = 0.67$ mA	$\xi_{y+} = 0.030$ at $I_{b-} = 0.55$ mA
$L = 10^{34}$ cm ⁻² s ⁻¹ at 1 [A] in LER	$L = 2.29 \times 10^{33}$ cm ⁻² s ⁻¹ at 0.265 [A] in LER	$L = 9 \times 10^{33}$ cm ⁻² s ⁻¹ at 1 [A] in LER extrapolation by a factor 4











$$\beta_x^* = 200 \text{ mm} \quad \beta_y^* = 4 \text{ mm}$$

Extremely low bunch current

15.8 mA/1576 bunches


to avoid beam-beam blowup as much as possible and to get geometrical luminosity.

0.1 mA/bunch

$$\Sigma_y = \sqrt{\sigma_{y-}^{*2} + \sigma_{y+}^{*2}} \quad \sigma_y^* = \Sigma_y / \sqrt{2}$$

LumiBelle2 is good performance !

Very large beam size ! →



$$\beta_x^* = 200 \text{ mm} \quad \beta_y^* = 4 \text{ mm}$$

Extremely low bunch current

15.8 mA/1576 bunches

to avoid beam-beam blowup as much as possible and to get geometrical luminosity.

0.1 mA/bunch

$$\Sigma_y = \sqrt{\sigma_{y-}^{*2} + \sigma_{y+}^{*2}} \quad \sigma_y^* = \Sigma_y / \sqrt{2}$$

LumiBelle2 is good performance !

Very large beam size ! →

Estimation from X-Ray Monitor:
 $\sigma_y^* = 400 \text{ nm (LER), } 500 \text{ nm (HER)}$



No change after adjustment of X-Y coupling (R₂) at IP

Measurement by beam-beam scan:

$\sigma_y^* = 1253 \text{ nm} \rightarrow 689 \text{ nm}$



Beam size becomes small !

Before R₂ adjustment




Luminosity Fit	RePlot	ReFit
Lum offset		1.105
σ_y [μm]		1.253
Vertical Offset [μm]		1.768
iBump V-offset target:		0.000

After R₂ adjustment



Luminosity Fit	RePlot	ReFit
Lum offset		1.279
σ_y [μm]		0.689
Vertical Offset [μm]		3.078
iBump V-offset target:		0.000

After R₂ adjustment





$$\beta_x^* = 200 \text{ mm} \quad \beta_y^* = 3 \text{ mm}$$

Extremely low bunch current
15.8 mA/1576 bunches
 to avoid beam-beam blowup as much as possible
 and to get geometrical luminosity.

0.1 mA/bunch

$$\Sigma_y^* = \sqrt{\sigma_{y-}^{*2} + \sigma_{y+}^{*2}} \quad \sigma_y^* = \Sigma_y^* / \sqrt{2}$$

$$\sigma_y^* = 333 \text{ nm}$$





The beam-beam parameter is 0.02.

The beam size from L_{sp} is consistent with that of no beam-beam.

$$L_{sp} = 4 \times 10^{31} \rightarrow \sigma_y^* = 300 \text{ nm} (\xi_y = 30 \text{ pm})$$

$$\leftrightarrow \xi_y = 23 \text{ pm for single beam in LER}$$



Luminosity drop at low current. issue in Phase 3



$$L_{sp} = \frac{L}{n_b I_+ I_-} = \frac{1}{4\pi(\sigma_z \phi_x) e^2 f_0 \sigma_y^*} = \frac{1.25 \times 10^{25}}{\sigma_y^*} [\text{cm}^{-2}\text{s}^{-1}/\text{mA}^2]$$

The beam-beam parameter is 0.02.

The beam size from L_{sp} is consistent with that of no beam-beam.

$$L_{sp} = 4 \times 10^{31} \rightarrow \sigma_y^* = 300 \text{ nm} (\epsilon_y = 30 \text{ pm})$$

$$\leftrightarrow \epsilon_y = 23 \text{ pm for single beam in LER}$$



Luminosity drop at low current. issue in Phase 3

$$L_{sp} = \frac{L}{n_b I_+ I_-} = \frac{1}{4\pi(\sigma_z \phi_x) e^2 f_0 \sigma_y^*} = \frac{1.25 \times 10^{25}}{\sigma_y^*} [\text{cm}^{-2}\text{s}^{-1}/\text{mA}^2]$$

The beam size from L_{sp} is consistent with that of no beam-beam.

$$L_{sp} = 4 \times 10^{31} \rightarrow \sigma_y^* = 300 \text{ nm} (\epsilon_y = 30 \text{ pm})$$

$$\leftrightarrow \epsilon_y = 23 \text{ pm for single beam in LER}$$



The beam-beam parameter is 0.02.

The beam-beam parameter is saturated at high bunch current. issue in Phase 3

$$\beta_y^* = 3 \text{ mm} \quad \text{LER: } \beta_x^* = 200 \text{ mm} \quad \text{HER: } \beta_x^* = 100 \text{ mm}$$

Beam size at IP estimated from luminosity

Beam size at IP estimated from X-Ray Monitor






$$\bar{\sigma}_y^* = \frac{\Sigma_y^*}{\sqrt{2}} \quad \Sigma_y^* = \sqrt{\sigma_{y-}^{*2} + \sigma_{y+}^{*2}} \quad L = \frac{N_+ H_- f_{col}}{2\sqrt{2}\pi\sigma_x^* \Sigma_y^*}$$


Beam size is large at the low bunch current in LER. Blowup is also significant at high bunch current.

Beam-Beam simulations with machine error (W-S)

K. Ohmi




Interference of Beam-Beam and lattice nonlinear degrades luminosity.



measured magnetic field
along beam axis
(N. Ohuchi)

Error field:
sextupole
skew sextupole
in QCS



Skew quadrupole corrector coils in QCS (for each main quads.)

Rotatable sextupoles in LER


Sextupole corrector coils in QCS

Skew sextupole corrector coils in QCS


Octupole corrector coils in QCS


skew quad-like coil

rotatable sextupole



Specific Luminosity is improving day by day.






	High bunch current		Reference		High current		Unit
	LER	HER	LER	HER	LER	HER	
I @ L_{peak}	265	217	327	279	788	778	mA
n_b	395		789		1576		
I/n_b	0.670	0.549	0.414	0.353	0.500	0.494	mA/bunch
ε_x	1.8	4.6	1.7	4.6	1.7	4.6	nm
β_x[*]	200	100	200	100	200	100	mm
β_y[*]	3	3	3	3	3	3	mm
v_x	44.562	45.542	44.558	45.541	44.561	45.545	
v_y	46.617	43.609	46.615	43.610	46.614	43.612	
σ_y[*] (XRM)	883	652	692	486	1285*	528	nm
σ̄_y[*] = Σ_y[*]/√2	797		552		879		nm
ξ_y	0.030	0.021	0.0277	0.0186	0.0244	0.0141	
L	2.29 x 10³³		2.62 x 10 ³³		5.55 x 10 ³³		cm ⁻² s ⁻¹

test of luminosity performance


typical physics run

*ε_y enhancement in LER


Daily Integrated Luminosity in Phase 2 (0 - 9am for 40 days) ONLINE Data



Issues in Phase 2





Compromise lifetime, injection, and detector background.




Number of movable collimators is small in LER. Especially, **only one in the vertical.**

Vertical Collimator


LER




HER



New collimator (SLAC type)






June 25

QCS quench (LER and HER)

LER vertical collimator has damage. Vacuum pressure rise was observed in the vicinity of the collimator.



July 9

QCS quench (HER)

HER vertical collimator has damage. Vacuum pressure rise was observed in the vicinity of the collimator. No bunch oscillation with beam loss

Beckoning cat (Fortune cat)



... To be continued in Phase 3

It is believed to draw happiness and customers.
"luminosity"

Appendix

Beam-Beam Parameter

$$\xi_{y\pm} = \frac{r_e N_{\mp}}{2\pi\gamma_{\pm}(\sigma_{x,eff}^*)} \sqrt{\frac{\beta_y^*}{\epsilon_y}}$$

$\beta_y^* \rightarrow \text{small} \rightarrow \xi_y \rightarrow \text{small} \rightarrow L \rightarrow \text{large}$

However

Luminosity

$$L = \frac{N_- N_+ n_b f_0}{4\pi(\sigma_{x,eff}^*)\sqrt{\epsilon_y\beta_y^*}} \simeq \frac{\gamma_{\pm}}{2er_e} \frac{I_{\pm}\xi_{y\pm}}{\beta_y^*}$$

Final Target

$I_{\pm} \rightarrow \times 2$ $\beta_y^* \rightarrow \times 1/20$ $\xi_y \rightarrow \times 1$ $L \rightarrow \times 40$

Beam-Beam Parameter

$$\xi_{y\pm} = \frac{r_e N_{\mp}}{2\pi\gamma_{\pm}(\sigma_{x,eff}^*)} \sqrt{\frac{\beta_y^*}{\epsilon_y}}$$

$\beta_y^* \rightarrow \text{small} \rightarrow \xi_y \rightarrow \text{small} \rightarrow L \rightarrow \text{large}$

However

Luminosity

$$L = \frac{N_- N_+ n_b f_0}{4\pi(\sigma_{x,eff}^*)\sqrt{\epsilon_y\beta_y^*}} \simeq \frac{\gamma_{\pm}}{2er_e} \frac{I_{\pm}\xi_{y\pm}}{\beta_y^*}$$

Final Target

$I_{\pm} \rightarrow \times 2$ $\beta_y^* \rightarrow \times 1/20$ $\xi_y \rightarrow \times 1$ $L \rightarrow \times 40$

Beam-Beam Parameter

$$\xi_{y\pm} = \frac{r_e N_{\mp}}{2\pi\gamma_{\pm}(\sigma_{x,eff}^*)} \sqrt{\frac{\beta_y^*}{\epsilon_y}}$$

$\beta_y^* \rightarrow \text{small} \rightarrow \xi_y \rightarrow \text{small} \xrightarrow{\text{However}} L \rightarrow \text{large}$

Luminosity

$$L = \frac{N_- N_+ n_b f_0}{4\pi(\sigma_{x,eff}^*)\sqrt{\epsilon_y\beta_y^*}} \simeq \frac{\gamma_{\pm}}{2er_e} \frac{I_{\pm}\xi_{y\pm}}{\beta_y^*}$$

Final Target

$I_{\pm} \rightarrow \times 2 \quad \beta_y^* \rightarrow \times 1/20 \quad \xi_y \rightarrow \times 1 \rightarrow L \rightarrow \times 40$

Beam-Beam Parameter

$$\xi_{y\pm} = \frac{r_e N_{\mp}}{2\pi\gamma_{\pm}(\sigma_{x,eff}^*)} \sqrt{\frac{\beta_y^*}{\epsilon_y}}$$

$\beta_y^* \rightarrow$ small \rightarrow $\xi_y \rightarrow$ small \rightarrow $L \rightarrow$ large

However

Luminosity

$$L = \frac{N_- N_+ n_b f_0}{4\pi(\sigma_{x,eff}^*)\sqrt{\epsilon_y\beta_y^*}} \simeq \frac{\gamma_{\pm}}{2er_e} \frac{I_{\pm}\xi_{y\pm}}{\beta_y^*}$$

Final Target

$I_{\pm} \rightarrow \times 2$ $\beta_y^* \rightarrow \times 1/20$ $\xi_y \rightarrow \times 1$ \rightarrow $L \rightarrow \times 40$

Beam-Beam Parameter

$$\xi_{y\pm} = \frac{r_e N_{\mp}}{2\pi\gamma_{\pm}(\sigma_{x,eff}^*)} \sqrt{\frac{\beta_y^*}{\epsilon_y}}$$

$\beta_y^* \rightarrow$ small \rightarrow $\xi_y \rightarrow$ small \rightarrow $L \rightarrow$ large

However

Luminosity

$$L = \frac{N_- N_+ n_b f_0}{4\pi(\sigma_{x,eff}^*)\sqrt{\epsilon_y\beta_y^*}} \approx \frac{\gamma_{\pm}}{2er_e} \frac{I_{\pm}\xi_{y\pm}}{\beta_y^*}$$

$\epsilon_y \rightarrow$ small

Final Target

$I_{\pm} \rightarrow \times 2$ $\beta_y^* \rightarrow \times 1/20$ $\xi_y \rightarrow \times 1$ \rightarrow $L \rightarrow \times 40$

Beam-Beam Parameter

$$\xi_{y\pm} = \frac{r_e N_{\mp}}{2\pi\gamma_{\pm}(\sigma_{x,eff}^*)} \sqrt{\frac{\beta_y^*}{\epsilon_y}}$$

$\beta_y^* \rightarrow$ small \rightarrow $\xi_y \rightarrow$ small \rightarrow $L \rightarrow$ large

However

Luminosity


$$L = \frac{N_- N_+ n_b f_0}{4\pi(\sigma_{x,eff}^*)\sqrt{\epsilon_y\beta_y^*}} \approx \frac{\gamma_{\pm}}{2er_e} \frac{I_{\pm}\xi_{y\pm}}{\beta_y^*}$$

$\epsilon_y \rightarrow$ small

Final Target


$I_{\pm} \rightarrow \times 2$ $\beta_y^* \rightarrow \times 1/20$ $\xi_y \rightarrow \times 1$ \rightarrow $L \rightarrow \times 40$

Ordinary collision (KEKB)




$\sigma = 4.5 \text{ mm}$


measurement at Belle



←→
bunch length x 2




Nano-Beam (SuperKEKB Phase2)




$\sigma = 550 \text{ }\mu\text{m}$

measurement at Belle II



The vertex distribution is constrained in the nano-beam scheme.




The same amount of rotation does not affect arc sections.

The global correction of XY couplings can not correct XY coupling at the IR completely.

XY coupling at IP remains locally.


Skew quads in QCS can be used to correct the local XY couplings.

XY couplings




LER

$\Delta s = -1.14$ mm




HER

$\Delta s = +0.4$ mm




IP XY coupling knob and dispersion knob


Skew quadrupole coils at sextupoles are utilized.




Beam size (XRM)

Luminosity





LER current: 320 mA
Touschek lifetime: 35 min (nb: 789)
lifetime (others): 80 min



HER current: 285 mA
Touschek lifetime: 86 min (nb: 789)
lifetime (others): 28 hours


Physical aperture limits the beam lifetime.

Movable collimators to reduce background and avoid QCS quench

ϵ_y is controlled by vertical dispersions.

ID number specifies a different set of sextupole combination.

5 sets of sextupole settings



June 27, 2018

2' : with optics correction
4' : with optics correction

σ_y measured by XRM

← Beam size larger


Beam size smaller →

Sextupole tuning could not improve the beam lifetime in the LER.

Physical aperture limits the beam lifetime. (Tracking simulation supports this.)


Luminosity run, May 29, 2018


H. Nakayama
slide from Phase 2 summary meeting




HER tune clearly affects the beam background.

We have to find better a working point and necessary to keep tunes.





**Pilot bunch
(non-collision)**



**Pilot bunch
(non-collision)**







Tunes are measured by gated tune meter.

optics server

We have applied tune feedback system for the last week of Phase 2.


optics server

Tune shift due to resistive wall is compensated.
(dependent on the beam current)





matching and send "set magnet" to optics server

Additional permanent magnets



**Threshold is much improved.
more than twice of 0.2 mA/bunch/RF bucket
Mode of CBI changes and the growth rate is reduced.**

Phase 1: June 9, 2016



Phase 2: July 12, 2019

